

SSO PROGRAM STATUS – MARCH 2013

Program Highlights

- 108 Active Projects
 - 37 Projects Completed (Nearly \$250M Construction Value)
 - 40 pump stations have been upgraded
 - Over 10,000 manholes have been inspected, rehabilitated, or replaced
 - Over 38 miles of force main improvements
 - Over 450 miles of gravity main improvements
 - 38 Projects Under Construction (Over \$600M Construction Value)
 - 33 Projects In Design (Over \$315M Construction Value)
- Over 350 Different Program Partners

Looking Ahead

The following projects are expected to advertise for construction bids during **1st quarter 2013**. As projects are advertised for construction bid, they will be posted on the SSO Program calendar at www.brprojects.com.

Little Farms Sewer Area Upgrades (11-FM-MS-036A AND 11-PS-MS-035A):

The project involves the installation of approximately 600 linear feet (lf) of forcemain ranging in diameter from 10" to 15," manholes, 400 lf of jack and bored pipe ranging from 10" to 15" in diameter, and 160 lf of 12" diameter horizontal directional drilling. The project also involves the installation of a new triplex pumping station as well as the removal of two existing pump stations and associated appurtenances and improvements. Expected to advertise March 2013.