



SSO PROGRAM STATUS – JUNE 2015

Program Highlights

- 110 active projects
 - 60 projects completed (over \$720 M construction value)
 - 30 projects under construction (nearly \$320 M construction value)
 - 20 projects in design (over \$240 M construction value)
- Over 450 Program partners

Looking Ahead

The following projects are expected to advertise for construction bids during the coming months. For more information visit www.brprojects.com.

Zachary Area Transmission Network Improvements Project Phase 5 (06-WC-IF-014E): The project will replace a pump station and improve piping. The new pump station will be able to hand a peak wet weather flow of 3,380 gpm.

East Blvd- Government St Area Rehabilitation Project (12-AR-MS-0041): This rehabilitation project consists of correcting defects in the system.

Airline Hwy Pipeline Project Group A (10-GS-MS-007A): This capacity project involves upsizing 4,520 LF of gravity main ranging between 8 and 24 in. in diameter and constructing 23,450 LF of force main ranging between 36 and 48 in. in diameter.

Airline Hwy Pipeline Project Group B (10-GS-MS-007B): This capacity project includes the installation of approximately 28,000 LF of gravity main ranging between 8 and 42 in. in diameter and approximately 50 LF force main in the south gravity central basin to increase sanitary sewer capacity. This project will also include approximately 1,000 LF of Jacked and Bored pipe ranging between 24 and 60 in. in diameter.

Sherwood Forest Blvd- Goodwood Blvd Sewer Area Upgrades (11-FM-MS-0005): This capacity project involves upsizing 14,760 LF of gravity main ranging between 8 and 36 in. in diameter and constructing 15,780 LF of force main ranging between 8 and 18 in. in diameter.