



# SSO PROGRAM STATUS – August 2016

---

## Program Highlights

- 110 total projects
  - 76 projects completed (over \$875 M construction value)
  - 26 projects under construction (nearly \$300 M construction value)
  - 8 projects in design (over \$60 M construction value)
- Over 450 Program partners

## Looking Ahead

The following projects are expected to advertise for construction bids during the coming months. For more information visit [www.brprojects.com](http://www.brprojects.com).

**Joor Rd-Greenwell Springs Rd Sewer Area Upgrades (11-FM-MS-0023):** This capacity project involves upsizing 4,960 LF of gravity main ranging between 10 and 12 in. in diameter and constructing 15,830 LF of force main ranging between 8 and 24 in. in diameter.

**Multiple Pump Stations: Prescott Road – Greenwell Springs Road (11-PS-MS-0034):** This pump station project involves upgrading or replacing 6 pump stations with peak wet weather pumping capacity between 840 GPM and 6,020 GPM.

**N 38th St. – Gus Young Ave Area Rehabilitation Project (14-AR-MS-0035):** This rehabilitation project consists of correcting defects in the system in the area of N 38th and Gus Young.

**Lovett Rd-Greenwell Springs Rd Sewer Area Upgrades (10-FM-MS-0049):** This capacity project involves upsizing 450 LF of gravity main with a diameter of 12 in. in diameter and constructing 46,550 LF of force main ranging between 8 and 36 in. in diameter.

**Flannery Rd - Florida Blvd Area Rehabilitation Project (Phase 2) (14-AR-MS-0034):** This Rehabilitation project consist of correcting defects in the system in the area of Flannery Rd and Florida Blvd.