

Burbank Rd - Gardere Ln Area Rehabilitation Project

City-Parish #08-AR-UF-0003

Advertisement for Bid: **4th Quarter 2008**
Project End: **4th Quarter 2010**

Rehabilitation of the sewer collection system is a comprehensive physical process that begins with cleaning and inspection of sewer pipes and manholes. Typical rehabilitation repairs include pipe and manhole replacement and trenchless technologies that minimize above ground disturbances such as cured-in-place pipe liners.



One of the first steps in rehabilitation includes a physical inspection of manholes and pipes to identify blockages.



Simply cleaning the pipes and manholes in preparation for the physical inspection removes blockages, debris and roots.



Burbank Rd - Gardere Ln Area Rehabilitation Project Facts

For this project:

- Approximately 168,300 linear feet of pipeline were inspected and rehabilitated
- Approximately 787 manholes were rehabilitated or replaced

Design Consultant:
Rehab Prog Mgmt Team

Construction Contractor:
Allen & LeBlanc

Estimated Construction Cost: \$6.1 M